BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work: Estimate for Construction of RCC Drains at Agrahara Layout in Ward No.05, Byatarayanapura Sub Division

		Estimate Cost Rs.						30000000.00	
Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2014-15	cum							
	Deslilting Of Drains								
	13th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	14th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	15th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	16th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	17th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	18th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	19th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	20th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	21th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	22th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	23th Cross 1st, 2nd and 3rd Main		4	56.00	0.45	0.45	45.36		
	10th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	11th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	12th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	13th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	16th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	17th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	18th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	19th cross 4th, 5th and 6th Main		4	56.00	0.45	0.45	45.36		
	20th cross 4th and 5th Main		4	64.00	0.45	0.45	51.84		
	21th cross 4th Main		4	56.00	0.40	0.30	26.88		
	1st Main		1X2	300.00	0.40	0.30	72.00		
	4th Main		1X2	250.00	0.60	0.45	135.00		
	5th Main		1X2	74.00	0.60	0.45	39.96		
							1187.52	146.88	**174423.00**
	Basic Rate	136.00							
	Area Weightage @ 8%	10.88							
	Total	**146.88**							
2	Removing B.S Slab of Drain and stacking Page No. 28/ Item No. 5.32/ PWD SR 2014-15	Sqm							
	13th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	14th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	15th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	16th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	17th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	18th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	19th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	20th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	21th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	22th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	23th Cross 1st, 2nd and 3rd Main		4	56.00	1.35		302.40		
	10th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	11th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	12th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	13th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	16th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	17th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	18th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	19th cross 4th, 5th and 6th Main		4	56.00	1.35		302.40		
	20th cross 4th and 5th Main		4	64.00	1.35		345.60		
	21th cross 4th Main		4	56.00	1.35		302.40		
	1st Main		1X2	300.00	1.35		810.00		
	4th Main		1X2	250.00	1.35		675.00		
	5th Main		1X2	74.00	1.35		199.80		
							8078.40		
	Deduct 25% Missing Slabs						2019.60		
							6058.80	58.32	**353349.00**
	Basic Rate	54.00							
	Area Weightage @ 8%	4.32							
	Total	**58.32**							
3	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 28/ Item No. 5.33/ PWD SR 2014-15	Sqm							
			Qty Vide Item No.3				6058.80		
							6058.80	**75.60**	**458045.00**
	Basic Rate	70.00							
	Area Weightage @ 8%	5.60							
	Total	**75.60**							
4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2014-15	**Sqm**							
	For Missing slabs (25%)						2019.60		
							2019.60	639.36	**1291251.00**
	Basic Rate	592.00							
	Area Weightage @ 8%	47.36							
	Total	**639.36**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
5	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in **Hard soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2014-15	Cum							
	For Solid Block Drain Raising Course								
	13th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	14th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	15th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	16th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	17th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	18th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	19th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	20th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	21th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	22th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	23th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.30	53.76		
	10th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	11th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	12th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	13th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	16th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	17th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	18th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	19th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.30	53.76		
	20th cross 4th and 5th Main		4x2	64.00	0.40	0.30	61.44		
	21th cross 4th Main		4x2	56.00	0.40	0.30	53.76		
	1st Main		2X2	300.00	0.40	0.30	144.00		
	4th Main		2X2	250.00	0.40	0.30	120.00		
	5th Main		2X2	74.00	0.40	0.30	35.52		
							1436.16	264.60	**380008.00**
	Basic Rate	245.00							
	Area Weightage @ 8%	19.60							
	Total	**264.60**							
6	KSRB-4-1.3 : Providing and laying in position **plain cement concrete of mix M 1:4:8** withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2014-15	**Cum**							
	For Solid Block Drain Raising Course								
	13th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	14th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	15th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	16th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	17th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	18th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	19th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	20th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	21th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	22th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	23th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.40	0.15	26.88		
	10th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	11th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	12th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	13th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	16th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	17th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	18th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	19th cross 4th, 5th and 6th Main		4x2	56.00	0.40	0.15	26.88		
	20th cross 4th and 5th Main		4x2	64.00	0.40	0.15	30.72		
	21th cross 4th Main		4x2	56.00	0.40	0.15	26.88		
	1st Main		2X2	300.00	0.40	0.15	72.00		
	4th Main		2X2	250.00	0.40	0.15	60.00		
	5th Main		2X2	74.00	0.40	0.15	17.76		
							718.08	4847.04	**3480562.00**
	Basic Rate	4488.00							
	Area Weightage @ 8%	359.04							
	Total	**4847.04**							
7	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 27/ Item No. 5.27/ PWD SR 2014-15	Sqm							
	For Solid Block Drain Raising Course								
	13th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	14th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	15th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	16th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	17th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	18th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	19th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	20th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	21th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	22th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	23th Cross 1st, 2nd and 3rd Main		4x2	56.00		0.40	179.20		
	10th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		
	11th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	12th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		
	13th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		
	16th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		
	17th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		
	18th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		
	19th cross 4th, 5th and 6th Main		4x2	56.00		0.40	179.20		
	20th cross 4th and 5th Main		4x2	64.00		0.40	204.80		
	21th cross 4th Main		4x2	56.00		0.40	179.20		
	1st Main		2X2	300.00		0.40	960.00		
	4th Main		2X2	250.00		0.40	800.00		
	5th Main		2X2	74.00		0.40	236.80		
							5785.60	993.60	**5748572.00**
	Basic Rate	920.00							
	Area Weightage @ 8%	73.60							
	Total	**993.60**							
8	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix **1:2:4** withOPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.6/ PWD SR 2014-15	**cum**							
	Coping Concrete Solid Block								
	13th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	14th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	15th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	16th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	17th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	18th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	19th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	20th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	21th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	22th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	23th Cross 1st, 2nd and 3rd Main		4x2	56.00	0.20	0.10	8.96		
	10th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	11th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	12th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	13th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	16th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	17th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	18th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	19th cross 4th, 5th and 6th Main		4x2	56.00	0.20	0.10	8.96		
	20th cross 4th and 5th Main		4x2	64.00	0.20	0.10	10.24		
	21th cross 4th Main		4x2	56.00	0.20	0.10	8.96		
	1st Main		2X2	300.00	0.20	0.10	24.00		
	4th Main		2X2	250.00	0.20	0.10	20.00		
	5th Main		2X2	74.00	0.20	0.10	5.92		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	For Vent								
	13th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	14th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	15th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	16th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	17th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	18th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	19th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	20th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	21th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	22th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	23th Cross 1st, 2nd and 3rd Main		4	56.00	0.40	0.10	8.96		
	10th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	11th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	12th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	13th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	16th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	17th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	18th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	19th cross 4th, 5th and 6th Main		4	56.00	0.40	0.10	8.96		
	20th cross 4th and 5th Main		4	64.00	0.40	0.10	10.24		
	21th cross 4th Main		4	56.00	0.40	0.10	8.96		
	1st Main		4	300.00	0.40	0.10	48.00		
	4th Main		2	250.00	0.40	0.10	20.00		
	5th Main		2	74.00	0.40	0.10	5.92		
							502.72	5327.64	**2678311.00**
	Basic Rate	4933.00							
	Area Weightage @ 8%	394.64							
	Total	**5327.64**							
9	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shutterng machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Matirial (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm							
	13th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	14th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	15th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	16th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	17th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	18th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	19th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	20th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	21th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	22th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	23th Cross 1st, 2nd and 3rd Main		4	56.00	0.90		201.60		
	10th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		
	11th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	12th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		
	15th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		
	16th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		
	17th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		
	18th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		
	19th cross 4th, 5th and 6th Main		4	56.00	0.90		201.60		
	20th cross 4th and 5th Main		4	64.00	0.90		230.40		
	21th cross 4th Main		4	56.00	0.90		201.60		
	1st Main		4	300.00	0.90		1080.00		
	4th Main		2	250.00	1.20		600.00		
	5th Main		2	74.00	1.20		177.60		
	For Additional Covering Slabs		2	275.00	0.90		495.00		
							6615.00	1856.67	**12281872.00**
	Data Rate	**1856.67**							
10	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum							
			Qty. Vide Item No. 1+5				**2623.68**		
							2623.68	67.32	**176626.00**
	Basic Rate Lead Charges Upto 2.00 Kms	5.12							
	PWD SR 2010-11 (P.118/I.17.1) For loading	62.20							
	Total	**67.32**							
							Grand Total		**27023019.00**
11	For 10% KRIDL Charges								**2702302.00**
12	For 1% Labour Welfare Cess								**270230.00**
13	Miscesallaneous Charges	L/S							**4499.00**
									30000000.00

Rupees Three Crore Only

Certificate:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR of 2014-15
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Assistant Engineer
KRIDL

Assistant Engineer
Ward No. 05(Jakkur)

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

ADMINISTRATIVELY SANCTIONED FOR Rs. 300.00 lacs
Rupees three crore only
Under Job No 0-005-13-000072

Techinical Manager
KRIDL

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Sub Division
Dt Estimate A/Sanctioned
Adl Com (Yz) AJ/1025/14-15
dated 5-9-2014 Rs 300.00 lacs

Addl Commissioner
(Yelahanka Zone)
BBMP. Bengaluru-92.

Technical Sanction for Rs.
Technical Sanction Accorded for Rs "300.00" LAKHS
is accorded under head
P2723
registered as CE No. 55 Dt: 05.09.14 Subject to Conditions contained in enclosed memo No. ../..Dr.
AE/JE TA DT (DTP) GE